

(N) 2x for plywood

braced panel splice

(where required)

(E) floor joists —

(N) L70 or L90 FFC —

A. GENERAL:

- All existing concrete and wood material which will be part of the strengthening work shall be in sound condition and free from defects which would substantially reduce the capacity of the material. Any substandard material shall be repaired or replaced to meet minimum building code requirements. New foundations shall meet current Building Code requirements.
- All metal connectors and hardware shall meet an approved standard for its intended use and be installed per manufacturer's instructions, and in accordance with the requirements of these standards. Alternate details may be approved by the building official provided detailed information and calculations are submitted and approved.
- All existing under floor ventilation shall be maintained
- 4. Due to the corrosive nature of new pressure treated wood which can cause premature failure of the metal hardware, fasteners in <u>new</u> pressure treated wood shall be hot dipped galvanized fasteners (meeting ASTM A153) and connectors (ASTM A 653 class G185 sheet), or better.

(E) = Existing construction; (N) = New construction 4/S1 = Refer to detail 4 on sheet S1 NTS = Not to scale ; Min = Minimum

FFC = Floor Framing Clip B. MUDSILL CONNECTIONS:

- . New bolts or UFP10 anchors required by reinforcement schedule 4/S1 shall be installed within plywood braced panels. See detail 2/S2
- Where an existing continuous rim joist, end joist, or solid blocking between joists, does not exist above the perimeter cripple wall or mud sill, new blocking and/or supplemental connections shall be provided and subject to approval by the building official.
- . All new mud sill bolts shall have a 3" X 3" X 1/4" plate washer installed between the mud sill (or blocking) and
- 4. New bolts shall be $1\frac{1}{2}$ " inches minimum from the edges of the mud sill and $\tilde{6}$ " from the ends.
- 5. Existing anchor bolts are generally not reliable and should not be considered as meeting the requirements of this

TECHNICAL NOTES

GENERAL INFORMATION

(N) vent holes

-(N) nailina patterr

see detail 4/S2

(N) plywood braced panel See detail 4/S2

6. New bolts or anchors within new braced panels shall be placed as follows:

- b) additional bolts or anchors at 32" on center or les c) additional foundation bolts or anchors as required by the
- New mudsill plates shall be pressure—treated douglas—fir or foundation-grade redwood.

schedule detail 4/S1

- 8. New steel bolts shall conform to ASTM A307. Adhesive or expansion type anchors shall be installed per manufacturer's instructions. Third party special inspection not required. Expansion bolts shall not be used whe the installation causes cracking of the foundation wall at the location of the bolt. The use of "adhesive type" anchors is strongly encouraged.
- 9. Provide new mudsill bolts or anchors outside of braced panels at 6'-0" on center or less.

C. FLOOR TO CRIPPLE WALL / MUDSILL **CONNECTION:**

- See "Reinforcement Schedule" 4/S1 and detail 5/S2 for required connection.
- 2. Increase length of nails $\frac{1}{2}$ " when attaching floor framing clips through plywood.
- 3. If splices in double top plates do not have a minimum 48 lap, provide a new minimum 4' strap. See detail 6A/S2.
- 4. Existing single top plates shall reinforced with a 16ga x 48" metal strap. See detail 6B/S2.
- 5. Where plate straps occur within a braced panel, the strap shall be placed over the plywood and the plywood nails omitted where the strap is installed.

D. PLYWOOD BRACED PANEL INSTALLATION:

- See 4/S1 "Reinforcement Schedule" for the required length of new plywood panel bracing along each wall line. See "Sample Foundation Plan" for the definition of a "wall line" and an example of plywood panel layout.
- Install plywood braced panels at each end of each wall line and space additional panels, as needed, along each wall line.
- 3. Plywood braced panels closest to the ends of wall lines shall be located as near to the ends as possible Panels may be located away from the ends of a wall line when existing obstructions or limited clearance necessitates
- . Plywood braced panels should be nearly equal in length and should be nearly equal in spacing along the length of the wall where possible.

5. The length of each individual panel must be twice the height of the cripple wall being braced, but never less than 48 inches in length.

The perimeter of all new plywood braced panel shall be nailed to existing cripple wall studs, top plate(s) and the mudsill at 4" on center. Attach plywood to intermediate cripple wall studs at a maximum of 12" on center.

GENERAL INSTRUCTIONS

DOES THIS PLAN SET APPLY TO YOUR HOME?

3. Is your home wood-framed construction?

5. Does your house have a crawl space?

answer this question as a YES.)

set for an example of a cripple wall)

4. Does the building have a continuous perimeter concrete foundation (ignoring the immediate area surrounding the fireplace? porches?)

6. Are all the cripple walls less than 4 feet in height?

(See detail 2/S1 in lower left corner of plan

7. If your home has brick or stone veneer along the exterior walls (excluding any chimneys), is the maximum height of the veneer 4 feet above the foundation? (If your home)

does not have any brick or stone veneer, you should

If the roofing of your home is clay tile, are the tiles installed without the use of mortar along the tile edges. (If your home's roofing is a material other than clay tile

you should answer this question as a YES.)

These plan set standards for strengthening may be approved by the building official without requiring additional plans or calculations. They provide an economical method to help

improve your home's chances of surviving an earthquake

The intent of these standards is to promote public safety

and welfare by reducing the risk of earthquake damage to existing wood—framed residential buildings.

existing Wood—Harrier residential consumer.

1. The requirements contained herein are prescriptive minimum standards intended to improve the seismic performance of residential buildings. They will not necessarily prevent earthquake damage, nor make your home earthquake proof. These recommendations are based on assumptions that apply the bases of average construction. You are encouraged to

to houses of average construction. You are encouraged to have a competent licensed engineer or architect review the

The prescriptive details and provisions are not intended to be the only acceptable strengthening methods permitted

(alternate details and methods may be used when approved

5. When the building official determines that conditions exist that are beyond the scope of these prescriptive standards, analysis and documentation shall be prepared by a California

this prescriptive plan does not legalize any previous work done without a permit.

Draw a scaled foundation plan of the house in the graph

2. Provide appropriate construction information in the "Construction Data", detail 5/S1. Determine the spacing requirements for the mudsill botts or anchor plates to be used and identify the type of FFC clip to be used.

Based upon the homes square footage, number of stories

and plywood layout plan". Detail 1/S1 for guidance).

space provided on sheet \$2 (refer to the "sample foundation

APPLICATION INSTRUCTION:

plans & modify them as appropriate for your home.

by the building official).

licensed architect or engineer.

plan details which represent:

IF YOU ANSWER NO TO ANY OF THESE QUESTIONS CONTACT YOUR LOCAL BUILDING DEPARTMENT FOR ASSISTANCE.

2. Is your home two stories or less?

To determine if your home qualifies please answer the

IF YOU ANSWER YES TO EACH OF THESE QUESTIONS, PROCEED TO APPLICANT INSTRUCTIONS.

following questions your home qualifies to use this standard

1. Is your home a one or two family residential \quad \quad \text{\texts} \quad \text{\texts}

following quetions. If you answer yes to all of the

READ FIRST:

- Nails shall be 8d common x 2½" long with a minimur shank diameter of .131 inches (.131 x 2½"). .131 x 2½" nails may be used for installations using nail guns.
- Plywood braced panel shall be 5-PLY, 15/32" exterior grade
- (3-PLY 1532" is not acceptable) Maintain or minimum eage distance 36", from center of nail to any plywood edge
- Do not overdrive, countersink, or otherwise damage the outermost ply" when installing nails"
- 11. Do not space nails closer than 3½" in plywood braced panels
- 12. Nails must be firmly embedded in framing behind plywood without causing splitting. See detail 4A/S2 for double stud at plywood joints.

E. PERMIT & INSPECTION REQUIREMENTS

- Submit a permit application and 2 completed plan sets t the Building Dept. for review (photographs of the mud sill, cripple wall, and floor framing conditions may assist the review process)
- Before starting work the permit holder may be required to schedule a pre-construction inspection with the building department to verify that field conditions are consistent with the information provided on the approved
- Inspections by the building department are required for:
- a) foundation bolt/anchor plate installation, b) installation of blocking,
- c) plywood braced panel installation on cripple wall,
- d) metal hardware installation, and e) final inspection
- No work requiring inspection shall be covered until it has been inspected and approved by the Building Department. Prior to final inspection, smoke detectors shall be installed
- in the attached dwelling(s) in accordance with building code requirements.

DEFINITIONS - "LIGHT" AND "HEAVY" CONSTRUCTION

HEAVY CONSTRUCTION is your home constructed using any of the following

- . Heavy roofing consisting of concrete or clay tiles (Weighing up to 11 pounds per square foot)

Clay tile weighing more than 11 pounds per square foot may be considered

LIGHT CONSTRUCTION is any building constructed using only the following

ROOFING MATERIALS:

- Composition or asphalt shingle
- Metal roofing (Weighing 5 pounds per square foot or less)

- Wood panel sheathing
- Wood board siding

5. This prescriptive plan addresses only seismic strengthening work. Alternative designs will be considered on a case—by—case basis. Work done under permit pursuant to

on an individual basis. Check w/ your local Building Department.

- Wood shakes or shingles

EXTERIOR WALL FINISHES

- Similar light board siding

		FOR CAPACITY) and Connection Description
	458 lbs.	L70 is 16 ga X 7" long uses (8) — 10d X 1-1/2" nails (.148 x 1 1/2")
	600 lbs.	L90 is 16 ga X 9" long uses (10) - 10d X 1-1/2" nails (.148 x 1 1/2")
	505 lbs.	H10 anchor uses (8) - 8d X 1-1/2" nails (.131 x 1 1/2")
	820 lbs.	1/2" dia. bolt
	1170 lbs.	5/8" dia. bolt

and type of construction "heavy" or "light", determine the requirements for "plywood bracing, mudsill anchorage" and floor to cripple wall/mudsill connections". Based on INTERIOR WALL FINISHES: 1. Gypsum board the "Reinforcement Schedule". See detail 4/S1. 2. Gypsum or plaster lath Identify on the "Foundation plan" the direction of run of all your floor joists. ldentify on the "foundation plan" (along the perimeter walls) the location of all fireplaces. i. For each wall segment on the foundation plan indicate the

ounas,	and Connection Description
S.	L70 is 16 ga X 7" long uses (8) - 10d X 1-1/2" nails (.148 x 1 1/2")
	L90 is 16 ga X 9" long uses (10) - 10d X 1-1/2" nails (.148 x 1 1/2")
i.	H10 anchor uses (8) - 8d X 1-1/2" nails (.131 x 1 1/2")
3.	1/2" dia. bolt
ıs.	5/8" dia. bolt
,	UED10 - Universal plate anchor

<u>_</u> C α Ш Δ S \geq ൧ ഗ Ш \mathbf{M}

APPLICANT

INFORMATION

ADDRESS:

TELEPHONE

OWNER

PROPERTY ADDRESS:

APPLICANT'S SIGNATURE

Z

П

П

'п г

RACING MED $\overline{\Delta}$ LL BR (7) Z Z Z W LE WALI \triangleleft S \triangleleft Z Ш

IGHT CR HENING PLAN FOR ANCHORAGE OF I TRENGTHENIN L PLATE ANC RESIDENTIAL S NO. TIVE SEIS ш SCRI ш

Ш Δ

2 TYPICAL CRIPPLE WALL BRACING DETAIL

1. This detail shows a sample cripple wall which has undergone a typical

2. This detail is not intended to supersede requirements contained in the specific installation details on sheet S2.

3. This isometric is viewed from the interior of the crawl space.

(N) mud sill connecti

anchor bolt @ 6'-0" a.c.

outside of (N) plywood

brand panels. See detail 2/S2

seismic retrofit.

(N) blocking

if required for flush

plywood installation

(N) optional UFP10-

per schedule 4/S1 (alternate)

(E) mudsill

Sée detail 2B/S2

MIN. NO. OF FLOOR FRAMING CLIPS (FFC)(MINIMUM SILL ANCHORS ALONG EACH WALL LINE ALONG EACH WALL LINE (4) TOTAL FLOOR 1/2"ø BOLT LIGHT CONSTRUCTION Light 16 12 19 Ligh N/A N/A N/A N/A N/A 3000

REINFORCEMENT SCHEDULE

PLYWOOD BRACING

FOOTNOTES FROM TABLE:

- See total floor area retrofit Construction Data. When UFP anchors and bolts are used in a single wall line, UFP anchors maybe substituted for the number of bolts.
 Not more than one angle per joist bay unless joists are spaced 24 inches on center.
- Where practicable install angles between joists above plywood braced panel locations. 4. Install L70 & L90 W/ 10d x $1\frac{1}{2}$ " nails (.148 x $1\frac{1}{2}$ ").
- H10 uses (8) 8d (.131" dia.) \times $1\frac{1}{2}$ " into joist and (8) 8d (.131" dia.) \times $1\frac{1}{2}$ " into top plates.

REINFORCEMENT SCHEDULE

GENERAL HOME INFORMATION:

A. Square footage calculation

 No. of stories above cripple wall/mud sill:
 Approximate 1st floor area over crawl space: (Do not include areas above garage slab) 3. Approximate 2nd floor area over crawl space:

CONSTRUCTION DATA

(Do not include areas above garage slab) Total floor area:

B. <u>Is your home of "Light" or "Heavy"</u> construction? 1. See detail 4/S1 for definition of heavy versus light construction

6. H10 floor framing clip should be used as an

alternate only where accessibility makes the use of L70 or L90 impractical. L70 and L90 clips are preferred over H10 FFC.

☐ - HEAVY construction ☐ - LIGHT construction

FLOOR FRAMING CONNECTION: to Mudsill or Top Plate

☐ FRAMING CLIP: Manufacturer Load Value parallel to cripple wall and/or mud sill

MUDSILL ANCHORAGE:

EXISTING

\Box	ROF12:	Diameter	Spacina
NΕV	٧		,
	BOLTS:	Diameter	Spacing
	Type:	□ Chemical	☐ Expansion/Mechanical
	ANCHOR	PLATE: Manu	ıfacturer '

Bolt Type: ☐ Chemical ☐ Expansion/Mechanical



EAST BAY CHAPTER

CC



California

₹ Bùilding

_ Officials

California Chapter

step1: the mud sill anchoring method. See detail 2/S2

step2; the floor-to-cripple wall/mudsill attachment. See det step3: the cripple wall bracing method to be used. See detail 4/


For each wall segment on the foundation plan indicate the maximum cripple wall height and the length and location o

all plywood braced panels to be installed (identify all wall sections that do not have cripple walls).





1 OF 2



APPLICANT INFORMATION

PROPERTY ADDRESS:

APPLICANT'S SIGNATURE

RACING

BR. AME

ALL

 \mathcal{O}

≫ □

0

RO FIS

щ О Ж

AN GE

교장

SZ

R

RIP. D F

S

 \mathcal{L}

<u>NOTE</u> — Technical changes may not be made without the express permission of the committee.

2 OF 2